**2U**

A 3.47" (88.1 mm)
B 6.00" (152.4 mm)
C 2.85" (72.4 mm)
D 0.56" (14.2 mm)

Large Horizontal Ring Panel

Used to organize horizontal cable runs. Large 2.8"H (71 mm) by 6"W (150 mm) heavy duty aluminum rings with rounded edges protect cable sheaths and will not bind during installation. Rings are bolted onto panels so they can be added or removed as needed. 19" and 23" wide rack panel options come pre-assembled with seven equally spaced rings.

• 2.8"H x 6"W (71 mm x 150 mm) heavy duty aluminum rings
• Rings can be added or removed as needed
• Installation hardware not included
• Shipping weight approximately 5 lb (2.3 kg)

| Part Number		Color
19"	**23"**	
11564-119	11564-123	Gray
11564-219	11564-223	White
11564-519	11564-523	Clear
11564-719	11564-723	Black

1U

1.72"
(43.7 mm)

Rack Cabling Managers

Used to organize horizontal cable and wire runs. Two sizes of slotted plastic rings provide ample room to hold all types and sizes of wiring and cabling.
• Easy to install on equipment racks
• Installation hardware not included

1175	Rack Cabling Managers

Panel/Ring Size H x D - in (mm)	
2	1U, 1.6 x 1.3 (41 x 33) Rings
3	2U, 3 x 1.6 (80 x 41) Rings

Color	
1	Gray
2	Computer White
5	Clear
7	Black

Rack Width	
19	19"W
23	23"W

1175	X	-	X	XX

2U

3.47"
(88.1 mm)