13934-7XX

13935-701

13928-001

Velocity® Cable Management Accessories

Cable Ring Kit

Creates a separate cable pathway on the back of a Velocity Single-Sided Vertical Cable Manager for premise cables. Attaches to the sides with included hardware. Match the kit to the width and height of the vertical cable managers; one kit per manager. Rings are C-shaped, 3.0"H x 7.7"D (76 mm x 196 mm), made from aluminum and painted black; latch is black plastic and spins open to provide access to cables. Cable opening on 3.6"W (91 mm) rings is 1.4"W (36 mm); cable opening on other rings is 3.8"W (97 mm). Each kit includes multiple rings and mounting hardware. The kit for 6' (1.8 m) include six rings, the kit for 7' (2.1 m) includes seven rings and the kit for the 8' (2.4 m) includes eight rings.

Cable Spool Kit

The Cable Spool Kit includes four small cable spools to provide slack management and strain relief for patch cords and jumper cables inside the Velocity Vertical Cable Managers. Attaches to the mid panel with included hardware. Use in 6"W (152 mm) or wider vertical cable managers; one kit per side. Spools are 2" (51 mm) in diameter and 6"L (152 mm) and made from aluminum; painted black. Each kit includes four spools and mounting hardware.

Cable Lashing Bar Kit

Provides tie points for cables inside Velocity Vertical Cable Managers. Attaches to the mid panel with included hardware. Use in 6"W (152 mm) or wider vertical cable managers; one kit per side. Bars are .23" (5.7 mm) in diameter; two bars are 23.7"L (602 mm); four bars are 16.6"L (422 mm), made from steel; zinc-plated, silver-colored. Each kit includes six lashing bars and mounting hardware.

Part Number	Description H x W ft (m) x in (mm)	Shipping Weight lb (kg)
13934-716	Cable Ring Kit for 6 (1.8) x 3.6 (91) Manager	8 (3.6)
13934-717	Cable Ring Kit for 7 (2.1) x 3.6 (91) Manager	9 (4.1)
13934-718	Cable Ring Kit for 8 (2.4) x 3.6 (91) Manager	11 (5.0)
13934-726	Cable Ring Kit for 6 (1.8) x 6 (152) Manager	9 (4.1)
13934-727	Cable Ring Kit for 7 (2.1) x 6 (152) Manager	11 (5.0)
13934-728	Cable Ring Kit for 8 (2.4) x 6 (152) Manager	12 (5.4)
13934-746	Cable Ring Kit for 6 (1.8) x 10 (254) Manager	12 (5.4)
13934-747	Cable Ring Kit for 7 (2.1) x 10 (254) Manager	14 (6.4)
13934-748	Cable Ring Kit for 8 (2.4) x 10 (254) Manager	15 (6.8)
13934-756	Cable Ring Kit for 6 (1.8) x 12 (305) Manager	14 (6.4)
13934-757	Cable Ring Kit for 7 (2.1) x 12 (305) Manager	16 (7.3)
13934-758	Cable Ring Kit for 8 (2.4) x 12 (305) Manager	18 (8.2)
13935-701	Cable Spool Kit, Pack of 4, Zinc	2 (0.9)
13928-001	Cable Lashing Bar Kit, Black	2 (0.9)

Cable ring kits are Black.